

Air conditioner. . . . . . . . . . . . drain.

Mount for check valves (3) . . . . . . . remove.

Clamp (2) ..... loosen.

Screw/hex. nut (1) ..... unscrew and pull pipes out of expansion valve.

Tighten to 10 ± 3 Nm.

Both screws (5) ..... unscrew and remove expansion valve. Tighten

to 8 ± 2 Nm.

Pipes and fittings on evaporator with dummy	
plugs	plug.
Reinstall	in reverse order; replace O-rings (83 and 84) as well as O-rings on evaporator pipes and moisten with refrigeration oil.
Fluid reservoir	replace (83-540).
Air conditioner	evacuate and recharge; test for proper function and leakage (83-508); allow engine to run at idle speed only for first 4 minutes.